



**National Housing Authority**  
Office of the Superintending Engineer  
Dhaka Circle  
Segunbagicha, Dhaka.

Tender No-25.38.0000.000.602.14.064.25-257

Date-03/05/2026

**Corrigendum of Tender invitation**

Ref.No. 25.38.0000.000.601.02.016.19- 132; Date: 02-04-2026  
Published on 07-04-2026

Following amendments have been made for the Remaining works of Construction of 1 no 14-storied Residential Flat Building with Single Basement Having 102 Nos 1575.00 sft Flats in each Building at Kallayanpur, (Revised Building No-14), Mirpur, Dhaka. (Tender ID: 1243197). E-Tender is invited in the National E-Gp Portal system (<http://www.eprocure.gov.bd>).

Sl.No.	BOQ.Item No	Original ( Description of Item / Description of Unit's/ Tender proposal Document last Selling Date & Time, Opening Date & Time)	Amended ( New Description of Item / Description of Unit's/ Tender proposal Document last Selling Date & Time, Opening Date & Time)
1	-	Selling Date : 07.04.2026 ; Time: 16:00 PM Opening Date :06.05.2026 ; Time: 16:00 PM	Selling Date : 12.05.2026 ; Time: 16:00 PM Opening Date : 13.05.2026 ; Time: 16:00 PM
2	03, 8(b)-8(o) & 11(A)	Cum	Sqm
3	05	sqm	cum
4	19(a), 19(b) (Vii), 19(c) (i), 19(d) (Vii), 19(e) (i), 19(f) (i), 19(g) (i) & 19(h) (vi)	Reinforced cement concrete works using steel shutter with minimum cement content relates to mix ratio 1:1.5:3 having minimum $f_{cr} = 30$ Mpa, and satisfying a specified compressive strength $f_c = 25$ Mpa at 28 days on standard cylinders as per standard practice of Code ACI/BNBC/ASTM & Cement conforming to BDS EN-197-1-CEM1, 52.5N (52.5MPa) / ASTM-C 150 Type - I, best quality Sylhet sand or coarse sand of equivalent F.M. 2.2 and 20 mm down well graded stone chips conforming to ASTM C-33, making, placing shutter in position and maintaining true to plumb, making shutter water-tight properly, placing reinforcement in position; mixing with standard mixer machine with hopper, fed by standard measuring boxes, casting in forms, compacting by vibrator machine and curing at least for 28 days, removing centering-shuttering after specified time approved, including cost of water, electricity, additional testing charges of materials and cylinders required by engineer, other charges etc. all complete approved and accepted by the Engineer. (Rate is excluding the cost of reinforcement and its fabrication, placing and binding etc)	Centering and shuttering, including strutting, propping etc. (The formwork must be rigid enough both in and out of plane, to make the concrete surface true to the designed shape and size by using necessary MS sheets of minimum 16 BWG, angles of minimum size 40 mm x 40 mm x 5 mm, flat bars etc.) and removal of form for.
5	49, 50 & 67	Each	Sqm

This Notice of Corrigendum will be treated as a part of this tender documents. All other terms and conditions of the tender will unchanged.

*Handwritten signature and date: 03.05.26*  
(Mr. Harjir Rahaman)  
Superintending Engineer  
Dhaka Circle  
National Housing Authority  
Segunbagicha, Dhaka.