

বাংলাদেশ পল্লী বিদ্যুতায়ন বোর্ড
BANGLADESH RURAL ELECTRIFICATION BOARD

নির্বাহী প্রকৌশলী (এসওডি) এর কার্যালয়
বাংলাদেশ পল্লী বিদ্যুতায়ন বোর্ড
আঞ্চলিক ওএন্ডএম কমপ্লেক্স
সিলেট-সুনামগঞ্জ বাইপাস রোড
মেদেনীমহল, সিলেট
মোবাইল : ০১৭১১-২৩১১৬৫
e-mail: brebxsylhet@gmail.com

স্মারক নং-২৭.১২.৯১৬২.০৫৮.৪৫.০০১.২০২৫. ১৮৫

তারিখ: ২০/০৪/২০২৫ খ্রীঃ

বিষয়ঃ “সিলেট আঞ্চলিক ওএন্ডএম কমপ্লেক্স এর প্রধান ফটকের অসমাপ্ত পূর্ত নির্মাণ কাজ সমাপ্ত করন” কাজের জন্য অনুরোধ জ্ঞাপন পদ্ধতিতে (RFQ) দরপত্র বিজ্ঞপ্তি।

প্রতি,

- ০১। নির্বাহী প্রকৌশলীর (এসওডি) কার্যালয়, বাংলাদেশ পল্লী বিদ্যুতায়ন বোর্ড, সিলেট এর অনুকূলে সরকারি তহবিল বরাদ্দ আছে। উক্ত তহবিলের আওতায় আঞ্চলিক ওএন্ডএম কমপ্লেক্স সিলেট-সুনামগঞ্জ বাইপাস রোড মেদেনীমহল, সিলেট-এর প্রজ্ঞানে “সিলেট আঞ্চলিক ওএন্ডএম কমপ্লেক্স এর প্রধান ফটকের অসমাপ্ত পূর্ত নির্মাণ কাজ সমাপ্ত করন” সংশ্লিষ্ট কাজে অভিজ্ঞ ঠিকাদারী প্রতিষ্ঠানের নিকট হতে নিম্নবর্ণিত শর্ত সাপেক্ষে নিজস্ব লেটার হেড প্যাডে সীল মোহরকৃত অনুরোধ জ্ঞাপন পদ্ধতিতে (RFQ) দরপত্র আহবান করা যাচ্ছে।
- ০২। নির্বাহী প্রকৌশলীর (এসওডি) কার্যালয়, বাংলাদেশ পল্লী বিদ্যুতায়ন বোর্ড, সিলেট এর “সিলেট আঞ্চলিক ওএন্ডএম কমপ্লেক্স এর প্রধান ফটকের অসমাপ্ত পূর্ত নির্মাণ কাজ সমাপ্ত করন” করতে ইচ্ছুক সকল কোটেশনদাতা কর্তৃক পরিদর্শনের জন্য অভিপ্রেত সংশ্লিষ্ট কাজের বিস্তারিত বিনির্দেশ, ডিজাইন এবং নকশা দপ্তর চলাকালীন সময়ে সকল কার্যদিবসে ক্রয়কারীর দপ্তরে প্রাপ্তিসাধ্য হবে।
- ০৩। এতদসংগে সংযুক্ত ‘কোটেসন দলিল’ ব্যবহার করে কোটেসন প্রস্তুত এবং দাখিল করতে হবে। কোটেসন দলিল ওয়েব সাইট [www.http://xenbreb.sylhet.gov.bd](http://xenbreb.sylhet.gov.bd) হতে ডাউনলোড করে কোটেসনের সকল শর্তাদি পূরণ করে দাখিল করতে হবে। এছাড়া নির্বাহী প্রকৌশলীর (এসওডি) কার্যালয়, বাংলাদেশ পল্লী বিদ্যুতায়ন বোর্ড, সিলেট হতে কোটেসন দলিল সংগ্রহ পূর্বক দর দাখিল করা যাবে।
- ০৪। নির্ধারিত কোটেসন দলিল যথাযথভাবে প্রস্তুতপূর্বক ক্ষমতাপ্রাপ্ত স্বাক্ষরকারী কর্তৃক প্রতিটি পৃষ্ঠা স্বাক্ষর করে ৬ অনুচ্ছেদে উল্লিখিত তারিখ ও সময়ে কোটেসন আহবানকারী কর্তৃক নির্ধারিত স্থানে নির্বাহী প্রকৌশলীর (এসওডি) কার্যালয়, বাংলাদেশ পল্লী বিদ্যুতায়ন বোর্ড, সিলেট আঞ্চলিক ওএন্ডএম কমপ্লেক্স, মেদেনীমহল, সিলেট-সুনামগঞ্জ বাইপাস রোড, সিলেট) রক্ষিত দরপত্র বাঞ্চে দাখিল/ জমা প্রদান করতে হবে।
- ০৫। কোটেসন দাখিল এবং পণ্য সরবরাহে কোনো জামানত যেমন, কোটেসন জামানত এবং কার্য-সম্পাদন জামানতের (যদি চুক্তি সম্পাদিত হয়) প্রয়োজন হবে না।
- ০৬। সিলমোহরকৃত কোটেসন খাম সরাসরি আগামী ২৪/০৪/২০২৫ খ্রীঃ তারিখ দুপুর ১২:০০ টা বা এর পূর্বে ৪নং অনুচ্ছেদে বর্ণিত স্থানে দাখিল করতে হবে। কোটেসনের খামে “জাতীয় পতাকা উত্তোলন ভিত্তিপ্রস্থ ও সৌন্দর্যবর্ধক পূর্ত নির্মাণ” -এর জন্য কোটেসন এবং আগামী ২৪/০৪/২০২৫ খ্রীঃ ১২:০৫ টার আগে খোলা যাবে না লিখে অবশ্যই সুস্পষ্টভাবে চিহ্নিত করতে হবে। উল্লিখিত সময়ের পরে প্রাপ্ত কোটেসন গ্রহণযোগ্য হবে না।
- ০৭। উপরে উল্লিখিত ৬ অনুচ্ছেদের বর্ণনা অনুযায়ী চিহ্নিত করা নির্ধারিত স্থানে প্রাপ্ত কোটেসনসমূহ/দরপত্র সমূহ আগামী ২৪/০৪/২০২৫ খ্রীঃ ১২:০৫ টায় ক্রয়কারীর ক্ষমতাপ্রাপ্ত কর্মকর্তা কর্তৃক উপস্থিত দাখিলকারীর সম্মুখে (যদি কেহ থাকেন) উন্মুক্ত/খোলা হবে।
- ০৮। কোটেসন দাখিলের নির্ধারিত সর্বশেষ তারিখ হতে ন্যূনতম ৬০ (ষাট) দিন পর্যন্ত জন্য সকল কোটেসন বৈধ থাকবে।
- ০৯। যদি চুক্তি সম্পাদন করা হয়, কোটেসনদাতার উদ্ধৃত দর বা মূল্যে মুনাফা ও ওভারহেড এবং সবধরনের কর, আবগারি শুল্ক, ভ্যাট, ট্যাক্স ও উৎসকর এবং আইনের অধীনে পরিশোধযোগ্য অন্যান্য চার্জ অন্তর্ভুক্ত থাকবে।



- ১০। দর টাকায় উদ্ধৃত করতে হবে এবং এ চুক্তির অধীন পরবর্তীতে মূল্য পরিশোধও টাকায় করা হবে। কোটেশন দাতার প্রস্তাবিত মূল্য, যদি গৃহীত হয়, তবে তা চুক্তিকালীন সময়ে স্থির অংকে থাকবে।
- ১১। কোটেশনদাতার চুক্তি করার আইনগত সক্ষমতা থাকতে হবে। কোটেশনদাতার যোগ্যতার প্রমাণস্বরূপ বৈধ ট্রেড লাইসেন্স, টিআইএন নম্বর ও ভ্যাট নিবন্ধন নম্বর এর সত্যায়িত অনুলিপি এবং কোনো তফসিলি ব্যাংক থেকে আর্থিক সচ্ছলতার সনদ দাখিল করতে হবে। এগুলো ব্যতীত কোটেশন অগ্রহণযোগ্য বলে বিবেচিত হবে।
- ১২। মূল্যায়ন কমিটি কোটেশনের সঙ্গে দাখিলকৃত তথ্য ও দলিলপত্রের ভিত্তিতে কোটেশন মূল্যায়ন করবে। চুক্তি সম্পাদনের জন্য সর্বনিম্ন মূল্যায়িত গ্রহণযোগ্য কোটেশন নির্ধারণের ক্ষেত্রে কমপক্ষে ৩ (তিন) টি গ্রহণযোগ্য কোটেশনের প্রয়োজন হবে।
- ১৩। উদ্ধৃত একক দর এবং মূল্যের মধ্যে অসঙ্গতি থাকলে একক দর প্রাধান্য পাবে। কথায় এবং সংখ্যার মধ্যে অসঙ্গতির ক্ষেত্রে কথায় উদ্ধৃত দর/মূল্য প্রাধান্য পাবে। মূল্যায়ন কমিটি কর্তৃক নির্ণীত গাণিতিক সংশোধন গ্রহণে কোটেশনদাতা বাধ্য থাকবে।
- ১৪। কার্যাদেশ জারীর তারিখ থেকে ৩০ (ত্রিশ) দিনের মধ্যে সকল কাজ সম্পন্ন করতে হবে।
- ১৫। নির্দিষ্ট সময়ের মধ্যে কার্যসম্পাদনে ব্যর্থ হলে প্রতিদিন বিলম্বের জন্য উদ্ধৃত মোট মূল্যের ১% এর $\frac{1}{30}$ অংশ বিলম্ব জরিমানা দাখিলকৃত বিল হতে কর্তন করা হবে। তবে জরিমানার পরিমাণ কোনোভাবেই মোট চুক্তি মূল্যের ১০ (দশ শতাংশ) এর অধিক হবে না। অন্যথায় কার্যাদেশ বাতিল পূর্বক প্রয়োজনীয় ব্যবস্থা গ্রহণ করা হবে।
- ১৬। “সিলেট আঞ্চলিক ওএন্ডএম কমপ্লেক্স এর প্রধান ফটকের অসমাপ্ত পূর্ত নির্মাণ কাজ সমাপ্ত করন” কাজের ক্রয়াদেশ প্রাপ্ত প্রতিষ্ঠান কর্তৃক নির্মাণ কাজ সম্পাদন করার পর তা ক্রয়কারী প্রতিষ্ঠানের উপযুক্ত প্রতিনিধি বা কর্মকর্তা কর্তৃক গুণগত মান যাচাই করা হবে। কাজের গুণগতমাণ সঠিক না হলে তা গ্রহণ করা হবে না। এছাড়া ত্রুটিপূর্ণ কাজ পাওয়া গেলে তা সরবরাহকারীকে নিজ দায়িত্বে পরিবর্তন করে দিতে হবে।
- ১৭। সন্তোষজনক কাজের পর হিসাবের খাতে প্রাপ্য চেকের মাধ্যমে দাখিলকৃত বিল পরিশোধ করা হবে।
- ১৮। ক্রয়কারী সকল কোটেশন বা ক্রয় কার্যক্রম বাতিল করার অধিকার সংরক্ষণ করে।
- ১৯। অবশ্যই অত্র নির্বাহী প্রকৌশলীর (এসওডি) কার্যালয়, বাংলাদেশ পল্লী বিদ্যুতায়ন বোর্ড, সিলেট আঞ্চলিক ওএন্ডএম কমপ্লেক্স, মেদিনীমহল, সিলেট-সুনামগঞ্জ বাইপাস রোড, সিলেট কর্তৃক প্রদত্ত/নির্ধারিত নমুনা মোতাবেক নির্মাণ কাজ সম্পন্ন করতে হবে।

কোটেশন আহবানকারী কর্মকর্তার স্বাক্ষর


(মোঃ সাহিদুল ইসলাম)
নির্বাহী প্রকৌশলী (এসওডি)
বাপবিবো, সিলেট।

বিতরণঃ (জ্যেষ্ঠতার ক্রমানুসারে নয়) বিজ্ঞপ্তি টি বহল প্রচারের উদ্দেশ্যে আপনার দপ্তরের নোটিশ বোর্ডে টানানোর অনুরোধ সহ।

- ০১। প্রধান প্রকৌশলী (প্রকল্প), বাপবিবোর্ড, ঢাকা।
- ০২। জেলা প্রশাসক, সিলেট।
- ০৩। পুলিশ সুপার, সিলেট।
- ০৪। প্রধান নির্বাহী কর্মকর্তা, জেলা পরিষদ, সিলেট।
- ০৫। নির্বাহী প্রকৌশলী, এলজিইডি/সড়ক ও জনপথ বিভাগ, সিলেট।
- ০৬। তত্ত্বাবধায়ক প্রকৌশলী, সিলেট জোন, বাপবিবো, সিলেট।
- ০৭। জেনারেল ম্যানেজার/সিনিয়র জেনারেল ম্যানেজার, পবিস-১/২/৩/৪।
- ০৮। নোটিশ বোর্ড।



(মোঃ জামির হোসেন)
সহকারী প্রকৌশলী

কোটেশন দাখিল পত্র
[প্রতিষ্ঠানের নির্ধারিত প্যাড ব্যবহার করুন]

স্মারক নং-২৭.১২.৯১৬২.০৫৮.৪৫.০০১.২০২৫.

তারিখ: ২০/০৪/২০২৫ খ্রিঃ

প্রতি

নির্বাহী প্রকৌশলীর (এসওডি)
বাংলাদেশ পল্লী বিদ্যুতায়ন বোর্ড, সিলেট
আঞ্চলিক ওএন্ডএম কমপ্লেক্স, মেদিনীমহল,
সিলেট-সুনামগঞ্জ বাইপাস রোড, সিলেট।

আমি/আমরা, নিম্ন স্বাক্ষরকারী, আঞ্চলিক ওএন্ডএম কমপ্লেক্স সিলেট-সুনামগঞ্জ বাইপাস রোড মেদিনীমহল, সিলেট-এর “সিলেট আঞ্চলিক ওএন্ডএম কমপ্লেক্স এর প্রধান ফটকের অসমাপ্ত পূর্ত নির্মাণ কাজ সমাপ্ত করন ” কাজ করার জন্য প্রস্তাব করছি।

আমার/আমাদের কোটেশনের মোট মূল্য , কথায়.....টাকা

আমার/আমাদের কোটেশন প্রদানের অনুরোধ জ্ঞাপনপত্রে (আরএফকিউ) উল্লিখিত সময়সীমা পর্যন্ত বৈধ থাকবে এবং আমি/আমরা এটা মানতে বাধ্য থাকব। বৈধতার মেয়াদ অতিক্রম হওয়ার পূর্বে যে কোনো সময় ইহা গ্রহণ করা যেতে পারে।

আমি/আমরা ঘোষণা করছি যে, আমার/আমাদের আপনার সঙ্গে চুক্তি সম্পাদনের আইনগত সক্ষমতা রয়েছে এবং বাংলাদেশ সরকার কর্তৃক কোনো দুর্নীতি, প্রতারণা, চক্রান্ত বা জবরদস্তিমূলক কর্মকাণ্ডে সম্পৃক্ততার দায়ে অযোগ্য ঘোষিত হইনি। এছাড়াও, আমি/আমরা অনুচ্ছেদ-১৯ (খ)-তে উল্লিখিত শর্তের বিষয়ে অবগত রয়েছি এবং কোটেশনে অংশগ্রহণের প্রতিযোগীতা বা সরবরাহ সম্পন্ন করার সময় এ ধরনের কাজে জড়িত না হওয়ার অঙ্গীকার করছি।

আমি/আমরা এই কোটেশন প্রদানের অনুরোধ জ্ঞাপন (আরএফকিউ) প্রক্রিয়ায় নিজের/নিজেদের নামে অথবা অন্যনামে বা ভিন্ন নামে একটার বেশি কোটেশন দাখিল করিনি। আমি/আমরা অবগত যে আপনার জারিকৃত ক্রয় আদেশের মাধ্যমে চুক্তি সম্পাদিত হবে এবং তা মানতে বাধ্য থাকব।

আমি/আমরা ২০ এপ্রিল ২০২৫ খ্রিঃ তারিখে আপনার জারিকৃত কোটেশন প্রদানের অনুরোধ জ্ঞাপন (RFQ) দলিলপত্র পরীক্ষা করেছি এবং এ সম্পর্কে আমাদের কোনো আপত্তি নেই।

আমি/আমরা অবগত যে, আমার/আমাদের কাছে কোনো দায় ছাড়াই আপনি সকল কোটেশন অথবা ক্রয় কার্যক্রম বাতিল করার অধিকার সংরক্ষণ করেন।



সিলসহ কোটেশনদাতার স্বাক্ষর
তারিখ

কার্যের পরিমাণ গত হিসাব সংবলিত বিবরণ (BoQ)


স্মারক নং-২৭.১২.৯১৬২.০৫৮.৪৫.০০১.২০২৫.

তারিখ: ২০/০৪/২০২৫ খ্রীঃ


Sl No	Description/ specifications of Items of Works	Unit	Quantity	Unit rates or prices quoted by the Quotationer (TK)		Total Amount (TK)
				In figures	In words	
1	2	3	4	5	6	7
1	Reinforced cement concrete works using wooden shutter, with minimum cement content relates to mix ratio 1:2:4 having minimum fcr = 26 Mpa, and satisfying a specified compressive strength f _c = 19 Mpa at 28 days on standard cylinders as per standard practice of Code ACI/BNBC/ASTM & cement conforming to BDS EN-197-1- CEM 1 52.5 N(52.5 Mpa) / ASTM-C 150 Type – I, best quality sand Sylhet sand or coarse sand of equivalent F.M. 2.2] and 20 mm down well graded stone chips conforming ASTM C-33 including screening, making, placing shutter in position and maintaining true to plumb, making shutter water-tight properly, placing reinforcement in position; mixing in standard mixer machine with hopper fed by standard measuring boxes, casting in forms, compacting by vibrator machine and curing at least for 28 days, removing centering-shuttering including cost of water, electricity, testing and other charges etc. all complete approved and accepted by the Engineer. (Rate is excluding the cost of reinforcement and its fabrication, placing and binding. all materials test fee borne by the bidder, no extra payment for this purpose. (a) Pedestals, column, miumn capital, lift wall and RCC wall	cum	10.81			
2	Brick works of width one brick or one and half brick length of first class bricks with cement sand (F.M. 1:2) mortar (1:6) in Supperstructure including raking out joints. tilling the interstices with mortar, deaning and soaking the brick at least for 24 hours before use and washing of sand, necessary scatfolding, curing at least for 7 days etc. all complete (measurement to given as 250 mm width for one brick length and 375 mm for one brick and a half brick length) and accepted by the Engineer-in-charge. (Cement: CEM-II/B-M)	cum	7.51			
4	Minimum 6 mm thick cement sand (F.M. 1:2) plaster (1:4) with fresh cement to ceiling, R.C.C. columns, beams, surface of stair case, sunshades, cornices, railings, drop wall, louvers, fins and finishing the corners and edges including washing of sand, cleaning the surface, curing at least for 7 days, cost of water, electricity, scaffolding and other charges etc. all	sqm	95.46			



	complete in all respect as per drawing and accepted by the Engineer-in-charge. (Cement: CEM-II/B-M) ground floor.					
5	Minimum 12 mm thick cement sand (F.M. 1.2) plaster (1:6) having with fresh cement to both inner and outer surface of wall, finishing the edges and corners including washing of sand, cleaning the surface, curing at least for 7 days, cost of water, electricity, scaffolding and other charges etc. all complete in all respect as per drawing and accepted by the Engineer-in-charge. (Cement: CEM-II/B-M)	sqm	9.74			
6	Grade 400 (B400DWR / B42-DWR: complying BDS ISO 6935-2:-2016 / ASTM A615) ribbed or deformed bar produced and marked according to Bangladesh standard, with minimum yield strenght, fy (ReH)= 400 Mpa but by fy not exceeding 480 Mpa and whatever is the actual yield strenght within allowable limit as per BNBC/ACI 318, the ratio of ultimate tensile strength fu to yield strength fy, shall be at least 1.25 and minimum elongation after fraclure and minimum total elongation at maximum force is 17% and 8% respectively:	kg	1498.50			
7	FORMWORK (wooden)for boundary wall, gale, centry post etc.	sqm	95.46			
	Providing brick works for 200 mm x 100 mm facing in superstructure with 200 mm x 100 mm x 50 mm machine made klinker hard pressed facing bricks of approved quality with cement sand (F.M. 1.2) mortar (1:4), including racking out joints, cutting the bricks to required size wherever necessary including high class recessed pointing, cleaning and soaking the bricks at least for 24 hours before use and washing and screening of sand, necessary scaffolding, curing at least for 7 days for all floors up to 4th floor including cost of water, electricity and other charges etc. all complete and accepted by the Engineer-in-charge. (100x200 mm face should be placed for facing). (Cement: CEM-II/B-M) In ground floor	sqm	21.64			
	Exterior premium acrylic emulsion paint of approved best quality and color with high performance against dirt picking tendency and efflorescence resistance properties along with water resisting properties and resistance properties against fungi, fading and flaking from authorized local agent of the manufacturer in a sealed container; applying to exterior surface with surface preparation including cleaning drying, making free from dirt, grease, wax, removing all chalked and scaled materials, fungus, mending good the surface defects using sand paper and necessary scaffolding; applying necessary exterior sealer of specified brand on prepared surface; then applying necessary exterior putty of specified brand for levelling, spot filling,	sqm	95.46			



crack filling and cutting by sand paper/zero water paper; finally applying 2 coats of exterior emulsion paint spreading by brush/roller/spray & necessary scaffolding etc. up to desired finishing, elapsing specified time for drying or recoating; all complete in all floors and accepted by the Engineer-in-charge.					
Concealed conduit point wiring (BYA) (without switch): Concealed conduit wiring for following point looping at the switch board with earth terminal with 1C-2x1.5 sqmm PVC insulated cable (BYA) & same size PVC insulated ECC (BYA) Green / White color including circuit wiring with 1C-2x2.5 sqmm PVC insulated cable (BYA) & same size PVC insulated ECC (BYA) (Green / White color) through PVC conduit (one conduit from switch board to common point on ceiling is considered to draw 3 pair of cable) of reputed manufacturer) of minimum 25 mm dia & 1.5 mm wall thickness complete with 18 SWG GP sheet / PVC switch board pull box with 3mm thick ebonite sheet cover, fixing materials etc. (without switch) as required including mending the damages good. All electrical contacts shall be of brass / copper connected through connector or soldering (no twisting shall be allowed) and cables shall be manufactured and tested according to relevant IEC / BDS / BS / VDE standards and as per detailed specification mentioned in Annexure-1. The work shall be carried out as per direction & approval of the Engineer.	Each	20.00			
Concealed wiring (BYA): Concealed conduit wiring with the following PVC insulated stranded cable (BYA) & PVC insulated Green / White colour ECC wire (BYA) through PVC conduit of reputed manufacturer complete with 18 SWG GP sheet pull box with 3mm thick ebonite sheet cover, fixing materials, other accessories etc. as required including mending the damages good. All electrical contacts shall be of brass / copper connected through connector or soldering (no twisting shall be allowed) and cables shall be manufactured and tested according to relevant IEC / BDS / BS / VDE standards and as per detailed specification mentioned in Annexure-1. The work shall be carried out as per direction & approval of the Engineer.	meter	250.00			
Providing & fixing on a prepared board 250 volt grade following single pole miniature circuit breaker (SPMCBS) having minimum breaking capacity 6-KA with thermal over-current and instantaneous electromagnetic short circuit release provision. (SPMCBS of DORMAN SMITH / MEM / SIEMENS / VIRTZRO / HAGER / FEDERAL / KAWAMURA / ABB / HAVELLS / LEGRAND / MERLIN GERIN / SCHNEIDER or equivalent brand accepted / approved by the engineer.) 16 Amps.	each.	3			



	Providing & fixing 250 volts. 5 / 6 amps (minimum) concealed type following switch / switch socket manufactured and tested in accordance with relevant IEC / VDE / NEMA / BS / JIS standards mounted on required size 18 SWG galvanized plain sheet / PVC board (Self-extinguishing 650oC) of 76.2 mm (3") depth. All electrical contacts shall be of brass / copper.					
13	One gang switch ----- -----	each.	4			
14	Two gang switch ----- -----	each.	8			
15	Supply & fixing of the following goodsmanufacturers by Dynamic/MEP/ Super Star/ TRANSTEC/ ENERGYPAC or equivalent brand accepted by the Engineer. Ceiling Rose	each.	20.00			
Total Amount (Inclusive of VAT and all applicable taxes)					Total Amount (in figure and words)	

Signature of the Quotationer with Seal

Date:

Name of Quotationer

টীকা:

- ১। কলাম ১, ২, ৩, ৪ ক্রয়কারী পূরণ করবে এবং কলাম ৬ ও ৭ কোটেশনদাতা পূরণ করবে।
- ২। যদি চুক্তি সম্পাদিত হয় তবে পণ্যের দর বা মূল্যে ক্রয়কারীর গ্রহণযোগ্য পণ্য এবং সংশ্লিষ্ট সেবা সরবরাহের স্থানে সর্বোত্তমভাবে সরবরাহের পরিবহন খরচ, বীমা খরচ ইত্যাদিসহ মুনাফা, ওভারহেড খরচ, সবধরনের কর, শুল্ক, ফী, লেভি ও প্রযোজ্য আইনের অধীন পরিশোধিত বা পরিশোধিতব্য যাবতীয় ব্যয় অন্তর্ভুক্ত থাকবে।
- ৩। সম্পাদিত কার্যের মূল্য পরিশোধ পুনঃপরিমাপ পদ্ধতিতে করা হইবে।

